



ADDENDUM | No. 1

PROJECT	Sanitary Sewer Lift Station Improvements - 2022
BID DATE	4:00 PM Local Time May 5 th , 2022
BID LOCATION	City Hall 202 North Broadway Ave Aurora, SD 57002
ISSUE DATE	May 2, 2022
NOTICE	Failure to acknowledge all addenda in the BID may cause rejection of the BID. See Instructions to Bidders.

SCOPE OF THIS ADDENDUM

The following becomes a part of the original project manual and drawings, taking precedence over the items that may conflict. The bidder shall note receipt and make acknowledgment of the Addendum on his/her bid form, incorporating its provision in his/her bid.

PRIOR APPROVALS

The following manufacturers of the items and materials have been added to the list of approved manufacturers. Listing of an item does not change the requirements of the specifications. Equipment furnished shall meet the materials and performance requirements as specified.

SECTION	DESCRIPTION	MANUFACTURER
	See PSE portion of addendum	

PROJECT MANUAL

The following additions, changes and clarifications have been made to the Project Manual.

SRF General Conditions with the Davis-Bacon & American Iron and Steel Provisions

Remove:

Form Debar-2

Replace:

Form Debar-2 (with SRF number C461081-03)



Section 33 3216 – Submersible Lift Station and Appurtenances,

Section 2.13, A,

Remove:

1. The maximum load rating shall be 1000 lbs.

Remove:

6. The model shall be Halliday Series DA Model D2A24D or equal.

Add:

6. The model shall be Halliday Series DA Model D3A24E or equal.

Section 40 9513 – LIFT STATION CONTROL PANEL AND HARDWARE,

Section 2.3, A,

Delete all text.

Add:

- A. Incoming service shall be per the Electrical Specifications as shown on Sheet E-900.

Section 2.5

Delete all text.

Insert: NOT USED

Section 2.6, A,

Delete all text.

Insert:

Provide circuit breakers on either side of the UPS to allow for power disconnect and short circuit protection for panel. Circuit breakers shall be provided and mounted on door of the control panel.

Section 2.7, A,

Delete all text.

Add:

- A. Surge capacitors rated 600 VAC RMS; three (3) poles, 1.0 mfd per pole; Delta CA 603R or equal.

Section 2.15

Delete all text.

Insert: NOT USED



Section 2.16

Delete all text.

Insert: NOT USED

Section 2.25, D,

Add:

"6. Khrone"

Section 2.26, C,

Remove:

"Omega PRTX94A 2"

Add:

"Automation Direct STH-N100100FT"

Section 2.27,

Add:

"2.27 GROUND LUG

- A. An equipment ground lug shall be provided for grounding the enclosure. The ground lug shall be suitable for the service provided to the enclosure sized per table 250-95 of the NEC. In all cases, the enclosure must be adequately grounded per Article 250 of NEC."

NOTE

The Plan Holders List and Addendums are available on our website at <http://www.bannerassociates.com> by clicking on **View Bid Information / Project Name / Project Information** link.




Project Manual and Drawing inquiries regarding the work should be directed to:

CONTACT PERSON(S)

Banner Associates, Inc.	Tel 1-605-692-6342 Toll Free 1-855-323-6342 Fax 1-605-692-5714	
Scot Leddy	Project Manager	scotl@bannerassociates.com
Subconsultant	Tel 1-320-978-8046	
Josh Mulder	Electrical Engineer	MulderJ@powersystem.org

ATTACHMENTS

- 1. Electrical Addendum No. 1
- 2. Debar - 2



Scot Leddy (P.E.) #14249

Electrical Addendum:

Project Name: Aurora Sanitary Sewer Lift Station Improvements – 2022

Electrical Addendum: Addendum No. E1

Date: April 29, 2022

Attachments: None

Item No. 1: Variable frequency drive (VFD) motor starters serving pump motors shall be rated as constant torque drives and be capable of serving a NEMA Code K motor.

Item No. : Refer to Specification Section 260480 – include Danfoss as an acceptable manufacturer.

Item No. 3: Provide (3) additional general purpose duplex receptacles in generator room on circuit #9. Place one of the additional receptacles on the north wall and one on either side of the overhead door.

United States Environmental Protection Agency
Washington, DC 20460

**Certification Regarding
Debarment, Suspension, and Other Responsibility Matters**

The prospective participant certifies to the best of its knowledge and belief that it and its principals:

- (a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency;
- (b) Have not within a three year period preceding this proposal been convicted of or had a civil judgement rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;
- (c) Are not presently indicted for or otherwise criminally or civilly charged by a government entity (Federal, State, or local) with commission of any of the offenses enumerated in paragraph (1)(b) of this certification; and
- (d) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State, or local) terminated for cause or default.

I understand that a false statement on this certification may be grounds for rejection of this proposal or termination of the award. In addition, under 18 USC Sec. 1001, a false statement may result in a fine of up to \$10,000 or imprisonment for up to 5 years, or both.

Typed Name & Title of Authorized Representative

Signature of Authorized Representative

Date

_____ I am unable to certify to the above statements. My explanation is attached.